

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

001

APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: ML-48194	6. SURFACE: State
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
2. NAME OF OPERATOR: XTO ENERGY INC.		8. UNIT or CA AGREEMENT NAME:	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. B CITY Farmington STATE NM ZIP 87401		PHONE NUMBER: (505) 324-1090	9. WELL NAME and NUMBER: State of Utah 17-8-7-34
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 212' FSL x 1430' FEL AT PROPOSED PRODUCING ZONE:		10. FIELD AND POOL, OR WILDCAT: Buzzard Bench, Ferron Sand	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approx. 5.5 miles northwest of Huntington, Utah		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 8E S	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) Approx 1500'		16. NUMBER OF ACRES IN LEASE: 1980.39	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) Approx 2500' (7-146)		19. PROPOSED DEPTH: 4,240	20. BOND DESCRIPTION:
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6610' GR		22. APPROXIMATE DATE WORK WILL START: 7/10/2005	23. ESTIMATED DURATION: 2 Weeks

24. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12 1/4"	8 5/8" J-55 24#	300	Class G +/- 200 sacks 1.18-1.16 15.6-15.8
7 7/8"	5 1/1" J-55 15.5#	4,125	Class G +/- 150 sacks 1.62 14.2

RECEIVED

JUN 06 2005

DIV. OF OIL, GAS & MINING

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) KYLA VAUGHAN

TITLE Regulatory Compliance Tech

SIGNATURE

DATE

Kyla Vaughan

6/2/05

(This space for State use only)

API NUMBER ASSIGNED: 43-015-30621

APPROVAL:

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 09-26-05

By: *[Signature]*

Range 8 East

S89°30'48"W - 2599.57'

S89°45'11"W - 2632.01'

(S89°48'W - 2699.74')

(S89°57'E - 2632.08')

NE Corner
(Elev. 6225')

NE Corner Sec. 12
T17S R7E
(Elev. 6508')

N00°15'47"W - 3086.49'
(NORTH - 3086.82')

N00°22'50"W - 2636.03'
(S00°03'E - 2636.04')

S00°21'40"E - 2630.24'
(N00°08'W - 2628.12')

N00°10'08"W - 3010.35'
(S00°05'W - 3004.98')

(N89°07'E - 5363.82')

N88°49'51"E - 2602.14'

N88°53'40"E - 2625.99'

Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

NOTE:

UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG
39°21'05.942"N
111°03'48.040"W

Location:

THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:

THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:

THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:


BASIS OF ELEVATION OF 6508.0' BEING AT THE NORTHEAST SECTION CORNER OF SECTION 12, TOWNSHIP 17 SOUTH, RANGE 7 EAST, SALT LAKE BASE & MERIDIAN, AS SHOWN ON THE RED POINT QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:

PROPOSED DRILL HOLE LOCATED IN THE SW 1/4 SE 1/4 OF SECTION 7; BEING 211.70' FROM THE SOUTH LINE AND 1429.60' FROM THE EAST LINE OF SECTION 7, T17S., R8E., SALT LAKE BASE AND MERIDIAN.

Surveyor's Certificate:

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.



TALON RESOURCES, INC.

195 North 100 West P.O. Box 1230

Huntington, Utah 84528

Phone (435)687-5310 Fax (435)687-5311

E-Mail talon@etv.net



State of Utah #17-8-7-34
Section 7, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By N. BUTKOVICH	Checked By L.W.J./A.J.S.
Drawing No. A-1	Date 4/12/05
	Scale 1" = 1000'
Sheet 1 of 4	Job No. 1711

GRAPHIC SCALE

0 500' 1000'
(IN FEET)
1 inch = 1000 ft.

Application for Permit to Drill

Company: **XTO Energy Inc.** Well No. **State of Utah 17-8-7-34**Location: **Sec. 7, T17S, R08E** Lease No. **ML - 48194**

All operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR § 3100 & 43 CFR § 3160), Onshore Oil and Gas Orders, the approved plan of operations and the conditions of approval. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

A. DRILLING PROGRAM**1. Surface Formation and Estimated Formation Tops:****Blue Gate Shale Member of the Mancos Shale (surface)****Ungraded Ground Elevation: 6,615.7'**

Formation	Sub-Sea	Well Depth
Top of Upper Ferron SS	2835'	3775'
Top of Ferron Coal	2800'	3810'
Bottom of Ferron Coal	2670'	3940'
Top of Lower Ferron SS	2670	3940'
Total Depth of Well	2375'	4240'

2. Estimated Depth at Which Oil, Gas, Water or Other Mineral Bearing Zones are Expected to be Encountered**Depth/Formation****Expected Oil Zones: No known oil zones will be penetrated****Expected Gas Zones: Gas bearing sandstones and coals will be penetrated from 3,775' to 3,940' KB.****Expected Water Zones: No known (aquifer) water zones will be penetrated. The gas bearing sandstones and coals may contain in-situ water.****Expected Mineral Zones: No know mineral zones will be penetrated.**

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and will be cased and cemented. When possible, water flow rates will be measured and samples will be taken and analyzed with the results being submitted to BLM. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment -include schematics of the BOP and choke manifold, and describe testing procedures: **See the attached BOP and Choke Manifold Schematic attached to this permit.**

BOP systems will be consistent with API RP 53 and Onshore Oil and Gas Order No. 2. Pressure tests of the surface casing and all BOP equipment potentially subject to pressure will be conducted before drilling the surface casing shoe. Blowout preventer controls will be installed prior to drilling the surface casing shoe and will remain in use until the well is completed or abandoned. Ram preventers shall be inspected and operated each trip (no more than once a day is necessary), and annular preventers shall be inspected and operated weekly to ensure good mechanical working order. These inspections shall be recorded in the drilling log and in the daily drilling report.

4. Casing Program and Auxiliary Equipment -include casing size, weight, grade, thread and coupling, setting depth and condition (new or acceptably reconditioned):

Hole size	Setting Depth	Size (OD)	Weight, Grade, Jt	Condition
12-1/4"	±300'	8-5/8"	24#, J-55, ST&C	N
7-7/8"	±4,240	5-1/2"	15.5#, J-55, ST&C	N

5. Cement -include the cement type, density, yield, additives and amount used in setting each casing string. Also include the anticipated cement fill-up. If stage cementing, describe techniques:

Surface Casing: ±200* sacks Class "G" (or equivalent) type cement with additives (typically LCM & accelerators) mixed at 15.6 – 15.8 ppg & 1.18 – 1.16 cuft/sx.

Surface casing shall be cemented back to surface. Centralizers shall be run, at a minimum, on the bottom three joints of each casing string.

* Cement volumes for permitting are calculated at 100% over gage hole. Actual cement volumes are calculated based on hole conditions during drilling and other factors. Actual cement volumes delivered to location range from 100% (minimum) to 300-400% over gage hole volume. Typically, an additional 200 sx of neat cement is also available, on location, for top out. If cement fails to circulate to surface or falls back from the surface, the well will be topped out using neat cement (meeting the above specifications) as necessary.

Production Casing: ±150* sacks Class "G" (or equivalent) type cement with additives (typically LCM, extenders, dispersant, thixotropic, fluid loss) mixed at 14.2 ppg & 1.62 cuft/sx.

Production casing will be cemented from TD to 500' above the top of the Upper Ferron Sandstone (as indicated by the geological top on the est. formation top's table).

* The volume shown is 50% over the gage hole volume calculated from TD to 500' above the top of the Ferron Sandstone. The actual volume will be obtained for the caliper log plus 50% excess from the actual well TD to 500' over the top of the

BOP SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

TESTING PROCEDURE

1. Test BOP after installation:

Pressure test BOP to 200-300
psig (low pressure) for 5 min.

Test BOP to Working Press or
to 70% internal yield of surf csg
(10 min).

2. Test operation of (both) rams on every trip.

3. Check and record Accumulator pressure on every tour.

4. Re-pressure test BOP stack after changing out rams.

5. Have kelly cock valve with handle available.

6. Have safety valve and subs to fit all sizes of drill string.

ROTATING HEAD
(OPTIONAL)

FILL UP LINE

FLOW LINE
TO PIT

PIPE
RAMS

BLIND
RAMS

TO CHOKE
MANIFOLD
2" dia min.

See Choke Manifold drawing for
specifications


HCR VALVE (OPTIONAL)

2" (MIN) FULL OPENING
VALVE

MUD CROSS

KILL LINE
2" dia min.


** Remove check or ball
from check valve and
press test to same press
as BOP's. **



CHOKES MANIFOLD SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

1. Stake all lines from choke manifold to pit.
2. Pressure test choke manifold after installation.
3. Pressure test manifold at the same time with the BOP Stack. Test manifold to the same test pressures.

TESTING PROCEDURE



Ferron Sandstone as shown on the actual log.

6. Mud Program and Circulating Medium -include mud components and weights. When air drilling, also include: length and location of blooie line; description of the auto igniter; description of the deduster equipment; and amounts, types and characteristics of stand-by mud:

Interval	Mud Type	Mud Weight	Viscosity
0' – 300'	Air	n/a	n/a
300' – TD	Air	n/a	n/a

The blooie line will be approx 100' in length and will extend in a straight line from below the rotating head as indicated in the BOP schematic. An automatic spark-type igniter will be affixed to the end of the blooie line and set to provide a continuous spark to ignite and burn any produced hydrocarbons and or gases. Dedusting, if necessary, will be accomplished with a small pump, waterline and spray nipple affixed near the end of the blooie line to provide a continuous spray of water. It is not planned to have any standby fluid on location, however if it is necessary to fill the hole with fluid, produced Ferron coal water is readily available and can be trucked to location as needed.

In the event the hole gets wet while drilling, either mist or produced Ferron coal water will be used as a circulating medium. In the event that produced Ferron coal water will not be adequate for mixing mud or is unusable for drilling, fresh water will be purchased, from town, and trucked to location.

Due to potential for contamination of usable quality water aquifers, chromates are banned from Federal leases.

Sufficient mud materials will be stored on location to maintain well control and combat lost circulation problems that might reasonable be expected.

7. Coring, Logging and Testing Program:

No cores or drill stem tests are planned for this well.

The well will be open hole logged with a triple combo logging suite consisting of array induction (if wet), compensated neutron, density, GR, caliper, SP (if wet) and Pe.

Initial opening of drill stem test tools will be restricted to daylight hours.

8. Abnormal Conditions, Bottom Hole Pressures and Potential Hazards -include anticipated bottomhole pressure and/or pressure gradient. Also list anticipated lost circulation zones, abnormal temperature zones and possible hydrogen sulfide bearing zones:

The maximum anticipated BHP gradient in any of the zones to be penetrated should be 8.33 ppg (fresh water). Lost circulation is a potential hazard in the Ferron coal section in the event the hole gets wet and water/mud must be used as the circulating medium.

No abnormal pressure, temperatures or dangerous gases (H2S) are anticipated.

9. Any Other Aspects of this Proposal that should be Addressed: None

B. THIRTEEN POINT SURFACE USE PLAN

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:

- a. Proposed route to location: **See Exhibit "A".**
- b. Location of proposed well in relation to town or other reference point:
The well location is approx 5.5 miles northwest of Huntington, Utah.
- c. Contact the County Road Department for use of county roads. The use of Emery County roads will require an encroachment permit from the Emery County Road Department.
- d. Plans for improvement and/or maintenance of existing roads: **None**
- e. Other:

2. Planned Access Roads:

- a. Location (centerline): **Starting from a point along an existing road in the SWSE of sec 7, T17S, R08E.**
- b. Length of new access to be constructed: **Approx 7,035' of new access will be constructed. See Exhibit "B".**
- c. Length of existing roads to be upgraded: **There is no existing access.**
- d. Maximum total disturbed width: **Typically 60' (max)**
- e. Maximum travel surface width: **25' or less**
- f. Maximum grades: **Maximum grades will not exceed 10% after construction.**
- g. Turnouts: **No turnouts are planned at this time.**
- h. Surface materials: **Only native materials will be used during construction. If necessary, gravel or rock maybe purchased an used to improve road conditions and travel.**
- i. Drainage (crowning, ditching, culverts, etc): **Roads will be crowned and bar ditches will be located along either side. 18-24" dia culverts will be installed as necessary.**
- j. Cattleguards: **No cattle guards are planned at this time. Cattle guards will be specified in the stipulations if necessary.**
- k. Length of new and/or existing roads which lie outside the lease or unit boundary for which a BLM/state/fee right-of-way is required: **None**

I. Other:

Surface disturbance and vehicular travel will be limited to the approved location and access road. Any additional area needed must be approved by BLM in advance.

If a right-of-way is necessary, no surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. The holder will adhere to conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.

If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of-way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.

If at any time the facilities located on public lands authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change) the BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental, or other financial obligations determined by the BLM.

If the well is productive, the access road will be rehabilitated or brought to Resource (Class III) Road Standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Field Office Manager will be notified so that temporary drainage control can be installed along the access road.

3. Location of Existing Wells -on a map, show the location of all water, injection, disposal, producing and drilling wells within a one mile radius of the proposed well, and describe the status of each: **See Exhibit "C"**
4. Location of Production Facilities:
 - a. On-site facilities: **Typical on-site facilities will consist of a wellhead, flow lines, artificial lifting system (pumping unit), wellhead compression, gas/water separator (2 phase), gas measurement and water measurement equipment, and a heated enclosure/building for weather and environmental protection.**
 - b. Off-site facilities: **Off-site facilities are located at the CDP station and typically include compression, processing, separation, tanks, pits, electronics, produced water disposal (SWD well) and gas measurement (sales meter).**
 - c. Pipelines: **The well will be produced into both a gas gathering pipeline and a produced water pipeline. The pipelines will be installed side by side in the same ROW traveling along the proposed access road and will be tied into the existing pipeline (gas/water) system already in place. See Exhibit "B" for the proposed pipeline route.**

- d. Powerlines: **A 3-Phase Power line will be laid along side the gas gathering pipeline and the water pipeline.**

All permanent (in place for six months or longer) structures constructed or installed (including oil well pumping units) will be painted a flat, nonreflective color to match the standard environmental colors, as determined by the Rocky Mountain Five-State Interagency Committee. All facilities will be painted within six months of installation. Facilities required by comply with the Occupational Safety and Health Act (OSHA) may be excluded. Colors will be as follows:

All site security guidelines identified in 43 CFR § 3162.7-5 and Onshore Oil and Gas Order No. 3 shall be followed, if applicable.

If a gas meter run, for sales, is constructed on location, it will be located on lease within 500 feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and will be buried downstream of the meter until it leaves the pad. Meter runs will be housed and/or fenced as necessary. The gas meter shall be calibrated prior to first sales and shall be calibrated quarterly thereafter. All gas production and measurement shall comply with the provisions of 43 CFR § 3162.7, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3, if applicable.

If a tank battery is constructed on this lease, it will be surrounded by a berm of sufficient capacity to contain 1½ times the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All oil production and measurement shall conform to the provisions of 43 CFR § 3162.7 and Onshore Oil and Gas Order No. 4, if applicable.

Production facilities on location may include a lined or unlined produced water pit as specified in Onshore Oil and Gas Order No. 7. If water is produced from the well, an application in conformance with Order No. 7 must be submitted, if applicable.

5. Location and Type of Water Supply:

All water needed for drilling purposes will be obtained from (describe location and/or show on a map): **All water required for drilling will typically be obtained and purchased from a local municipal water supply. If possible, currently produced coal well water may also be used after receiving the necessary permits and permission, if necessary. Water will be trucked to location by a third party trucking company who specializes in water hauling.**

Water obtained on private land, or land administered by another agency, will require approval from the owner or agency for use of the land.

6. Source of Construction Material:

Pad construction material will be obtained from (if the source is Federally owned, show location on a map): **All construction material will be purchased from private landowners or from a commercial gravel/materials pit.**

The use of materials under BLM jurisdiction will conform to 43 CFR § 3610.2-3, if applicable.

7. Methods of Handling Waste Disposal:

Describe the methods and locations proposed for safe containment and disposal of waste material, e.g. cuttings, produced water, garbage, sewage, chemicals, etc.

The reserve pit will typically be lined with a synthetic material, ±12 mils in thickness.

The reserve pit will be located along the edge and within the boundaries of the designated wellpad and the walls of this pit will be sloped at no greater than 2 to 1.

The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. As soon as the reserve pit has dried, all areas not needed for production will be rehabilitated.

Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.

8. Ancillary Facilities: **No ancillary facilities will be required during the drilling or completion of the well.**

9. Well Site Layout -depict the pit, rig, cut and fill, topsoil, etc. on a plat with a scale of at least 1"=50'. **See Exhibit "D" & "E".**

All wells, whether drilling, producing, suspended, or abandoned, will be identified in accordance with 43 CFR § 3162.6.

Access to the well pad will be from the: **North**

The blooie line will be located: **at least 100 feet from the well head.**

To minimize the amount of fugitive dust and spray escaping from the blooie pit, the following blooie line deflection method will be employed: **Water Injection**

10. Plans for Restoration of the Surface:

The top 6 inches of topsoil material will be removed from the location and stockpiled separately on: **Adjacent Land**

Topsoil along the access road will be reserved in place adjacent to the road.

Within 30-45 days after completion of well, all equipment that is not necessary for production shall be removed.

The reserve pit and that portion of the location not needed for production will be reclaimed 90-120 days after completion of the well.

Before any dirt work to restore the location takes place, the reserve pit must be ready for burial.

All road surfacing will be removed prior to the rehabilitation of roads.

Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle use.

All disturbed areas will be recontoured to replicate the natural slope.

The stockpiled topsoil will be evenly distributed over the disturbed area.

Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.

Seed will be broadcast or drilled between September and November, or at a time specified by the BLM and or state. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.

The following seed mixture will be used: **As specified in the conditions of approval.**

If necessary, an abandonment marker will be one of the following, as specified by BLM:

- 1) at least four feet above ground level,
- 2) at restored ground level, or
- 3) below ground level.

In any case the marker shall be inscribed with the following: operator name, lease number, well name and surveyed description (township, range, section and either quarter-quarter or footages).

Additional requirements: **None**

11. Surface and Mineral Ownership: **Both the surface and the minerals are owned by the State of Utah.**

12. Other Information:

a. Archeological Concerns: **There are no archeological concerns that the operator is aware of at this time.**

The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the BLM Field Office. Within five (5) working days, the BLM will inform the operator as to:

- whether the materials appear eligible for the National Register of Historic Places;

- the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

- a time frame for the BLM to complete an expedited review under 36 CFR § 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the BLM are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the BLM will assume

responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The BLM will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the BLM that the required mitigation has been completed, the operator will then be allowed to resume construction.

- b. Threatened and Endangered Species Concerns: **None**
- c. Wildlife Seasonal Restrictions: **Current wildlife restrictions and closure dates are specified in the BLM's Environmental Impact Statement.**
- d. Off Location Geophysical Testing: **None**
- e. Drainage crossings that require additional State or Federal approval: **None**
- f. Other:

13. Lessee's or Operator's Representative and Certification

Representative:

Name: **Jeffrey W. Patton**

Title: **Drilling Engineer**

Address: **2700 Farmington Ave, Ste 1 , Bldg K
Farmington, NM 87410**

Phone No.: **(505) 324-1090**

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by **XTO Energy Inc.** and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided by **XTO Energy Inc.** This statement is subject to the provisions of 18 U.S.C. § 1001 for the filing of a false statement.

Kyla Vaughan for Jeff Patton


Signature

Drilling Engineer

Title

Date

6/2/05




TN * MN
12°


0.0 0.5 1.0 1.5 2.0 2.5 3.0 3.5 miles
0 1 2 3 4 5 km

Map created with TOPO!® ©2003 National Geographic (www.nationalgeographic.com/topo)

TALON RESOURCES
195 North 100 West PO BOX 1230
Huntington, UT 84528
(435) 687-5310

EXHIBIT A





TALON RESOURCES, INC.

195 N. 100 W., P.O. Box 1230
Huntington, Utah 84528
Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



State of Utah #17-8-7-34
Section 7, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By:
N. BUTKOVICH

Drawing No.
L-1

4 of 4

Checked By:
L.W.J.



Date: 4/12/05

Scale:
1" = 200'

Job No.
1711

EXHIBIT C

ELEVATION OF UNGRADED GROUND AT LOCATION STAKE = 6615.7'
ELEVATION OF GRADED GROUND AT LOCATION STAKE = 6613.7'



TALON RESOURCES, INC.

195 North 100 West P.O. Box 1230

Huntington, Utah 84528

Phone (435) 687-5310 Fax (435) 687-5311

E-Mail talon@etv.net



LOCATION LAYOUT

Section 7, T17S, R8E, S.L.B.&M.
State of Utah #17-8-7-34

Drawn By:
N. BUTKOVICH

Checked By:
L.W.J.

Drawing No.

Date: _____

A-2

4/12/05


Scale:
1" = 50'

Sheet 2 of 4


Job No.
1711

EXHIBIT D


EXHIBIT E



1"=10'
X-Section
Scale
1"=40'



SLOPE = 1 1/2 : 1
(EXCEPT PIT)
PIT SLOPE = 1 : 1



TALON RESOURCES, INC.
195 North 100 West P.O. Box 1230
Huntington, Utah 84528
Phone (435)687-5310 Fax (435)687-5311
E-Mail taloneetv.net

TYPICAL CROSS SECTION Section 7, T17S, R8E, S.L.B.&M. State of Utah #17-8-7-34	
<small>Drawn By:</small> N. BUTKOVICH	<small>Checked By:</small> L.W.J.
<small>Drawing No.</small> C-1	<small>Date:</small> 4/12/05
	<small>Scale:</small> 1" = 40'
<small>Sheet</small> 3 <small>of</small> 4	<small>Job No.</small> 1711

APPROXIMATE YARDAGES
CUT
(6")TOPSOIL STRIPPING = 820 CU. YDS.
REMAINING LOCATION = 2,630 CU, YDS.
(INCLUDING TOPSOIL STRIPPING)
TOTAL CUT (INCLUDING PIT) = 3,500 CU. YDS.
TOTAL FILL = 1,965 CU. YDS.

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

003

APD RECEIVED: 06/06/2005

API NO. ASSIGNED: 43-015-30621

WELL NAME: ST OF UT 17-8-7-34

OPERATOR: XTO ENERGY INC (N2615)

CONTACT: KYLA VAUGHAN

PHONE NUMBER: 505-324-1090

PROPOSED LOCATION:

SWSE 07 170S 080E

SURFACE: 0212 FSL 1430 FEL

BOTTOM: 0212 FSL 1430 FEL

EMERY

BUZZARD BENCH (132)

LEASE TYPE: 3 - State

LEASE NUMBER: ML-48194

SURFACE OWNER: 3 - State

PROPOSED FORMATION: FRSD

COALBED METHANE WELL? YES

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	Dled	7/8/05
Geology		
Surface		

LATITUDE: 39.35161

LONGITUDE: -111.0628

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 104312762)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. MUNICIPAL)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:


___ R649-2-3.
Unit HUNTINGTON CBM
___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
___ R649-3-3. Exception
___ Drilling Unit
Board Cause No: 245-2
Eff Date: 4-25-2001
Siting: Suspends General Siting
___ R649-3-11. Directional Drill

COMMENTS:

Needs Permit (06-28-05)

STIPULATIONS:

1- STATEMENT OF BASIS



OPERATOR: XTO ENERGY INC (N2615)

SEC: 7 & 20 T. 17S R. 8E

FIELD: BUZZARD BENCH (132)

COUNTY: EMERY

CAUSE: 245-2 / 4-25-2001

Wells


- ✱ GAS INJECTION
- ✱ GAS STORAGE
- ✱ LOCATION ABANDONED
- ⊕ NEW LOCATION
- ⬢ PLUGGED & ABANDONED
- ✱ PRODUCING GAS
- PRODUCING OIL
- ✱ SHUT-IN GAS
- ✱ SHUT-IN OIL
- ✱ TEMP. ABANDONED
- TEST WELL
- ▲ WATER INJECTION
- ◆ WATER SUPPLY
- ⬢ WATER DISPOSAL

Units.shp

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Fields.shp

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 10-JUNE-2005

From: LaVonne Garrison
To: Diana Whitney
Date: 6/24/2005 2:47:12 PM
Subject: Re: New APDs for XTO Energy Inc. - Huntington CBM Unit

These locations were approved as part of their 2005 POD. However, the State 17-8-20-22 has been misdescribed on their plan. It was described in the SWNE rather than the SENW. I will have them revise their POD with the new location.

>>> Diana Whitney 06/10/05 9:45 AM >>>
Hi LaVonne,

(Proposed PZ Ferron)

43-015-30620	State of Utah	17-8-4-21	Sec. 4	T. 17S	8E	804 FNL	1788 FWL
43-015-30621	State of Utah	17-8-7-34	Sec. 7	T. 17S	8E	212 FSL	1430 FEL
43-015-30622	State of Utah	17-8-15-14	Sec. 15	T. 17S	8E	1130 FSL	1165 FWL
43-015-30623	State of Utah	17-8-20-22	Sec. 20	T. 17S	8E	2026 FNL	1992 FWL
43-015-30624	State of Utah	17-8-22-21	Sec. 22	T. 17S	8E	950 FNL	1448 FWL

Thank you,
Diana

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: XTO Energy Inc.

WELL NAME & NUMBER: State of Utah 17-8-7-34

API NUMBER: 43-015-30621

LEASE: State **FIELD/UNIT:** Buzzard Bench, Ferron Sand

LOCATION: 1/4, 1/4 SENW **Sec:** 7 **TWP:** 17 S **RNG:** 8 E 212 **FSL** 1430 **FEL**

LEGAL WELL SITING: F **SEC. LINE;** F 1/4, 1/4 **LINE;** F **ANOTHER WELL.**

GPS COORD (UTM): X =4355793 E; Y =494478 N **SURFACE OWNER:** SITLA

PARTICIPANTS

Bart Kettle (DOGM), Nathan Sill (DWR), Allen Childs (Talon Resources Inc), Ray Peterson (Emery County), Gary Hancock and dirt contractor (Nelsons Construction).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Proposed location is ~4.5 miles northwest of Huntington, located in Emery County Utah. Location is surrounded by rangelands with many steep gullies and dry wash's cutting through a series of mesas rising to the east. Drainages flow into the San Rafeal River and eventually to the Green River 60 miles away. The well site is located in an 10-12" precept zone at the base of the eastern portion of the Wasatch Plateau. A majority of the surface is bare ground, spares vegetative cover is due to salty clay soils and an arid climate. Agriculture lands are located along the valley floor to the east. With the exception of agriculture lands to the east and montane forest to the west in the upper elevations of the Wasatch Plateau the regional topography is arid rangelands dominated by Salt Scrub shrublands and Pinion/Juniper woodlands. There where no perennial streams or springs observed in close proximity to the location. Drainages in the immediate area are dry washes, flowing water during the extreme rain events of the monsoon season and during spring snow melt.

SURFACE USE PLAN

CURRENT SURFACE USE: Seasonal livestock grazing, late winter/spring big game habitat, rodent habitat, and OHV recreational use.

PROPOSED SURFACE DISTURBANCE: 7,035 of new road will be built. Maximum travel surface will be ~25'. Well pad will be 170'x260'.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: State of Utah "AA" 7-106, Rowley 8-111, State of Utah "BB" 8-113, State of Utah "AA" 7-105

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Facilities consisting of a wellhead, flow lines, lifting system, separator measurement equipment and enclosed building for measurement equipment will be located on-site. A pipeline for transport of produced gas and water will run from this well and tie into an existing line along the access road.

SOURCE OF CONSTRUCTION MATERIAL: On location or local sources.

ANCILLARY FACILITIES: None

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST OR CONCERNS?
(EXPLAIN): Limited public interest or concern is anticipated during drilling and production of this well.

WASTE MANAGEMENT PLAN:

Reserve pit will be lined and fenced to allow fluids too evaporate. Once dry the reserve pit contents will be buried in place, back fill will be sufficiently deep so that no liner is exposed. Trash must be contained in a trash cage and hauled away top an approved disposal site as necessary but no later than at the completion of drilling operations.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: Dry washes, no live water was observed in close proximity to the well pad or access road.

FLORA/FAUNA: Mule Deer, Elk, Blacktail jackrabbits, raptors, rodents and lizards. Grasses: Crested wheat grass. Shrubs: Four wing salt brush, Green stem rubber rabbit brush, white stem rubber rabbit brush, Birchleaf mountain mahogany, winterfat, skunk sumac, broom snakeweed, Mormon tea and antelope bitter brush. Trees: Utah Juniper and Two-needle pinyon. Forbs: Yellow eyed cryptantha and rocky mountain aster, annual Flixweed, scented penstemon, penny cress. Other: Harriman's yucca

SOIL TYPE AND CHARACTERISTICS: Silty clay loam, large sand stone boulders.

SURFACE FORMATION & CHARACTERISTICS: Blue Gate Member of the Mancos Shale/clay and alluvial outwash. Soils at the well site are somewhat depositional in nature and are generally fine with large sandstone boulders.

EROSION/SEDIMENTATION/STABILITY: Soils are slightly erosive to stable, prone to wind and water erosion when disturbed. Construction of a well pad at this site is not expected to contribute significant sediment loads into the local watershed.

PALEONTOLOGICAL POTENTIAL: None noted

RESERVE PIT

CHARACTERISTICS: 44'x80'x8'

LINER REQUIREMENTS (Site Ranking Form attached): Lining is required.

SURFACE RESTORATION/RECLAMATION PLAN

Well site and immediate area will be cleared of debris and material not needed for production after the completion of drilling. Reclamation will start when the reserve pit is dry. All areas not needed for production will be back filled. Reclaimed areas will be broadcast seeded in late fall or winter with specified seed mixture.

SURFACE AGREEMENT: As per SITLA mineral lease.

CULTURAL RESOURCES/ARCHAEOLOGY: On file

OTHER OBSERVATIONS/COMMENTS

Emery county request that access roads be graveled and maintained at the merge point with county roads by the operator. DWR present, but no input provided. Well site appears to be in mule deer winter range, but no drilling restrictions requested. XTO intends to install a liner in the reserve pit even though a liner is not required based on the on-site evaluation.

ATTACHMENTS

Photos of this location were taken and placed on file.

Bart Kettle
DOGM REPRESENTATIVE

07/01/2005 12:30 p.m.
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>0</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>5</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 20 (Level I Sensitivity)

Sensitivity Level I = 20 or more: total containment is required, consider criteria for excluding pit use.

Sensitivity Level II = 15-19: lining is discretionary.

Sensitivity Level III = below 15: no specific lining is required.



JUN 28 2005

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: XTO Energy Inc.
WELL NAME & NUMBER: State of Utah 17-8-7-34
API NUMBER: 43-015-30621
LOCATION: 1/4, 1/4 SESE Sec: 7 TWP: 17 S RNG: 8 E 212 FSL 1430 FEL

Geology/Ground Water:

The well will spud into a poorly to moderately permeable soil that is developed on the Upper part of the Blue Gate Member of the Mancos Shale. Local outcrops dip into the Wasatch Plateau at about 5° to the northwest. Although no aquifers with high quality ground water are likely to be encountered, the Lower, Middle and Upper units of the Emery Sandstone could potentially contain an aquifer. The proposed surface casing and cementing program should be extended to contain all three units of the Emery Sandstone to ensure the protection of any unknown ground water resources. A search of the Division of Water Rights records indicates that no water rights have been filed on subsurface water within a mile of the location.

Reviewer: Christopher J. Kierst

Date: July 6, 2005

Surface:

On-site conducted June 28, 2005. In attendance: Bart Kettle (DOGM), Ray Peterson (Emery County), Allen Parker (Talon Resources Inc.), Nathan Sill (DWR), Gary Hancock (XTO) and dirt contractor representative (Nelsons Construction) invited but choosing not to attend Ed Bonner (SITLA).

Emery County requested that operator gravel and maintain access road at merge point with county road. Reserve pit liner would be required at this well site. Planned pipelines for produced water and gas would follow access road to existing pipeline.

Reviewer: Bart Kettle **Date:** 07-01-05

Conditions of Approval/Application for Permit to Drill:

1. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.



State Online Services

Agency List

Business.utah.gov

Search Utah.gov




UTAH DIVISION OF WATER RIGHTS

WRPLAT Program Output Listing

Version: 2004.12.30.00 Rundate: 07/06/2005 04:57 PM

Radius search of 5280 feet from a point N212 W1430 from the SE corner, section 07, Township 17S, Range 8E, SL b&m
Criteria:wrtypes=W,C,E podtypes=all status=U,A,P usetypes=all



0 700 1400 2100 2800 ft

Water Rights

WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
<u>93-227</u>	Point to Point 0 0 08 17S 8E SL		P	19020000	S	0.000	0.000	UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS ADMIN. 675 EAST 500 SOUTH, SUITE 500
<u>93-230</u>	Point to Point N990 W1150 E4 08 17S 8E SL		P	19020000	S	0.000	0.000	CHARLES HOMER & RUTH L. ROWLEY HUNTINGTON UT 84528
<u>93-231</u>	Point to Point S1850 E250 N4 08 17S 8E SL		P	18750000	S	0.000	0.000	CHARLES HOMER & RUTH L. ROWLEY HUNTINGTON UT 84528
<u>93-3120</u>	Point to Point 0 0 07 17S 8E SL		P	18600000	S	0.000	0.000	PACIFICORP AN OREGON CORPORATION UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS ADMIN.
<u>93-3370</u>	Point to Point 0 0 08 17S 8E SL		P	18600000	S	0.000	0.000	675 EAST 500 SOUTH, SUITE 500 CHARLES HOMER & RUTH L. ROWLEY HUNTINGTON UT 84528
<u>93-347</u>	Point to Point N990 W300 E4 08 17S 8E SL		P	18680000	S	0.000	0.000	UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS
<u>93-3612</u>	Point to Point		P	18750000	S	0.000	0.000	

	0 0 18 17S 8E SL					ADMIN. 675 EAST 500 SOUTH, SUITE 500 UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS ADMIN.
<u>93-410</u>	Point to Point	P	19020000 S	0.000	0.000	675 EAST 500 SOUTH, SUITE 500 SAMUEL HERBERT ROWLEY HUNTINGTON UT 84528
	0 0 07 17S 8E SL					STATE OF UTAH BOARD OF WATER RESOURCES 1594 WEST NORTH TEMPLE, STE 310 HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-555</u>	Point to Point	P	18680000 S	0.000	0.000	P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY
	0 0 08 17S 8E SL					
<u>93-1063</u>	Rediversion	U	19610330 DIS	0.000	130800.000	
	S550 W400 N4 08 17S 8E SL					
<u>93-1136</u>	Rediversion	P	18920000 DIMOSP	0.000	2025.000	
	S1320 W300 N4 08 17S 8E SL					
<u>93-1136</u>	Rediversion	P	18920000 DIMOSP	0.000	2025.000	
	S840 E2480 NW 08 17S 8E SL					

<u>93-1137</u>	Rediversion	P	18900000 DIMOSP 0.000	3274.710	IRRIGATION COMPANY P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S1320 W300 N4 08 17S 8E SL				
<u>93-1137</u>	Rediversion	P	18900000 DIMOSP 0.000	3274.710	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S840 E2480 NW 08 17S 8E SL				
<u>93-1138</u>	Rediversion	P	18900000 DIMOSP 0.000	50.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S1320 W300 N4 08 17S 8E SL				
<u>93-1138</u>	Rediversion	P	18900000 DIMOSP 0.000	50.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S840 E2480 NW 08 17S 8E SL				
<u>93-1139</u>	Rediversion	P	18900000 DIMOSP 0.000	58.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S1320 W300 N4 08 17S 8E SL				
<u>93-1139</u>	Rediversion	P	18900000 DIMOSP 0.000	58.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY

	S840 E2480 NW 08 17S 8E SL				P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-221</u>	Surface	P	18750000 DM	150.000 0.000	
	S840 E2480 NW 08 17S 8E SL				P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-2211</u>	Surface	P	18790000 IS	45.000 0.000	
	S1320 W300 N4 08 17S 8E SL				C/O J. CRAIG SMITH & DAVID B. HARTVIGSEN HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-2212</u>	Surface	P	18840000 IS	77.250 0.000	
	S1320 W300 N4 08 17S 8E SL				P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-2213</u>	Surface	P	18880000 IS	80.000 0.000	
	S1320 W300 N4 08 17S 8E SL				P.O. BOX 327 HUNTINGTON CLEVELAND IRRIGATION COMPANY
<u>93-2226</u>	Surface	P	18790000 DM	45.000 0.000	
	S840 E2480 NW 08 17S 8E SL				P.O. BOX 327

<u>93-2227</u>	Surface	P	18840000 DM	77.250	0.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S840 E2480 NW 08 17S 8E SL					
<u>93-2228</u>	Surface	P	18880000 DM	80.000	0.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY P.O. BOX 327
	S840 E2480 NW 08 17S 8E SL					
<u>93-239</u>	Surface	P	18750000 IS	150.000	0.000	HUNTINGTON CLEVELAND IRRIGATION C/O J. CRAIG SMITH & DAVID B. HARTVIGSEN
	S1320 W300 N4 08 17S 8E SL					
<u>93-3195</u>	Rediversion	A	19800228 DIMOSP	0.000	2000.000	HUNTINGTON CLEVELAND IRRIGATION C/O J. CRAIG SMITH & DAVID B. HARTVIGSEN
	S1320 W300 N4 08 17S 8E SL					
<u>93-3195</u>	Rediversion	A	19800228 DIMOSP	0.000	2000.000	HUNTINGTON CLEVELAND IRRIGATION C/O J. CRAIG SMITH & DAVID B. HARTVIGSEN
	S840 E2480 NW 08 17S 8E SL					
<u>93-928</u>	Rediversion	A	19160725 DIMOSP	0.000	600.000	HUNTINGTON CLEVELAND

					IRRIGATION COMPANY
	S1320 W300 N4 08 17S 8E SL				P.O. BOX 327
<u>93-928</u>	Rediversion	A	19160725 DIMOSP 0.000	600.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY
	S840 E2480 NW 08 17S 8E SL				P.O. BOX 327
<u>93-950</u>	Rediversion	A	19210112 DIMOSP 0.000	465.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY
	S1320 W300 N4 08 17S 8E SL				P.O. BOX 327
<u>93-950</u>	Rediversion	A	19210112 DIMOSP 0.000	465.000	HUNTINGTON CLEVELAND IRRIGATION COMPANY
	S840 E2480 NW 08 17S 8E SL				P.O. BOX 327
<u>93-951</u>	Rediversion	A	19220803 DIMOSP 0.000	9892.620	HUNTINGTON CLEVELAND IRRIGATION COMPANY
	S1320 W300 N4 08 17S 8E SL				P.O. BOX 327
<u>93-951</u>	Rediversion	A	19220803 DIMOSP 0.000	9892.620	HUNTINGTON CLEVELAND IRRIGATION COMPANY

	S840 E2480 NW 08 17S 8E SL					P.O. BOX 327
<u>a14107</u>	Rediversion	A	19800228 DIMSPX	0.000	3000.000	STATE OF UTAH BOARD OF WATER RESOURCES 1594 WEST NORTH TEMPLE, STE 310
	S1320 W300 N4 08 17S 8E SL					STATE OF UTAH BOARD OF WATER RESOURCES 1594 WEST NORTH TEMPLE, STE 310
<u>a14107</u>	Rediversion	A	19800228 DIMSPX	0.000	3000.000	STATE OF UTAH BOARD OF WATER RESOURCES 1594 WEST NORTH TEMPLE, STE 310
	S840 E2480 NW 08 17S 8E SL					PACIFICORP DBA UTAH POWER & LIGHT COMPANY ATTN: CARLY BURTON
<u>a15762</u>	Rediversion	A	19900730 IMP	0.000	31264.000	PACIFICORP DBA UTAH POWER & LIGHT COMPANY ATTN: CARLY BURTON
	S1320 W300 N4 08 17S 8E SL					PACIFICORP DBA UTAH POWER & LIGHT COMPANY ATTN: CARLY BURTON
<u>a15762</u>	Rediversion	A	19900730 IMP	0.000	31264.000	PACIFICORP AN OREGON CORPORATION 1407 WEST NORTH TEMPLE SUITE 110
	S840 E2480 NW 08 17S 8E SL					HUNTINGTON- CLEVELAND IRRIGATION COMPANY
<u>a25003</u>	Surface	A	20001010 S	0.000	1.000	
	N190 W182 SE 01 17S 7E SL					
<u>a25346</u>	Surface	A	20010315 IS	0.000	344.800	

S662 E2449 NW

08 17S 8E SL

P.O. BOX 327
HUNTINGTON-
CLEVELAND
IRRIGATION
COMPANY

<u>a3812</u>	Rediversion	A	19601102 I	0.000	10000.000
--------------	-------------	---	------------	-------	-----------

S550 W400 N4
08 17S 8E SL

P.O. BOX 327

<u>E2504</u>	Surface	A	19870326 M	0.000	325.000
--------------	---------	---	------------	-------	---------

CASTLE VALLEY
SPECIAL SERVICE
DISTRICTS600 E2480 NW
08 17S 8E SL

P. O. BOX 877

[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

Well name:	07-05 XTO St of Ut 17-8-7-34		
Operator:	XTO Energy Inc.		Project ID:
String type:	Surface		43-015-30621
Location:	Emery County		

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 79 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 300 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 264 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 262 ft

Completion type is subs
Non-directional string.

Re subsequent strings:

Next setting depth: 4,125 ft
Next mud weight: 8.600 ppg
Next setting BHP: 1,843 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	14.4

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	1370	10.465	300	2950	9.83	6	244	38.78 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: July 8, 2005
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	07-05 XTO St of Ut 17-8-7-34	
Operator:	XTO Energy Inc.	Project ID:
String type:	Production	43-015-30621
Location:	Emery County	

Design parameters:

Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 133 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 3,264 ft

Burst

Max anticipated surface pressure: 1,348 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,843 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Completion type is subs
Non-directional string.

Tension is based on buoyed weight.
Neutral point: 3,588 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4125	5.5	15.50	J-55	ST&C	4125	4125	4.825	129.3
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1843	4040	2.192	1843	4810	2.61	56	202	3.63 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: July 8, 2005
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 4125 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Casing Schematic

Manco's Shale

Surface

8-5/8"
MW 8.4
Frac 19.3

TOC @
0.

Surface
300. MD

✓ w/18% washcoat
~~Debris in casing~~
~~Max 1000' max water~~
~~shale~~

BHP

$$(0.52)(4125)(8.6) = 1844$$

G₂

$$(6.2)(4125) = 495$$

$$\text{MASP} = 1349$$

Emerg S.S.

BOPE - 2,000 ✓

Surf/Csg - 2950

$$70\% = 2005$$

Max pressure @ Surface Shoe = 1003

Propose Test to 2000# ✓

✓ Adequate DCD 7/8/05

✓ propose TOC ± 500 above
Top Ferron S.S.

TOC @
3264.

w/15% washcoat

3775' Top Ferron S.S.

~~max 1000' max water~~

3940' Top of Lower Ferron S.S.

5-1/2"
MW 8.6

Production
4125. MD

From: Ed Bonner
To: Whitney, Diana
Date: 9/6/2005 12:46:56 PM
Subject: Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

Dominion Exploration & Production, Inc

AP 1-2J
AP 2-2J
AP 3-2J
AP 5-2J
AP 8-2J
AP 9-2J
AP 10-2J
AP 15-2J

EnCana Oil & Gas (USA) Inc
Middle Mesa State 36-14-29-24

EOG Resources, Inc
East Chapita 6-16
East Chapita 7-16
East Chapita 8-16

The Houston Exploration Company

Rock House 13-36
Asphalt Wash 3-16-11-24
Asphalt Wash 4-16-11-24
Asphalt Wash 7-16-11-24
Asphalt Wash 8-16-11-24
Asphalt Wash 12-16-11-24
Asphalt Wash 14-16-11-24
Gusher 6-2

QEP Uinta Basin, Inc
SC 4ML-16-10-23
SC 5ML-16-10-23
SC 12ML-16-10-23
SC 14ML-16-10-23
RW 01-36BG

XTO Energy Inc
State of Utah 17-8-7-34
State of Utah 17-8-15-14

If you have any questions regarding this matter please give me a call.

CC: Garrison, LaVonne; Hill, Brad; Hunt, Gil

**State of Utah****Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

September 6, 2005

XTO Energy, Inc.
2700 Farmington Ave, Bldg K, Ste. 1
Farmington, NM 87410

Re: State of Utah 17-8-7-34 Well, 212' FSL, 1430' FEL, SW SE,
Sec. 7, T. 17 South, R. 8 East, Emery County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-015-30621.

Sincerely,

A handwritten signature in black ink, appearing to read "Gil Hunt".

Gil Hunt
Associate Director

pab
Enclosures

cc: Emery County Assessor
SITLA
Bureau of Land Management, Moab District Office

Operator: XTO Energy, Inc.
Well Name & Number State of Utah 17-8-7-34
API Number: 43-015-30621
Lease: ML-48194

Location: SW SE Sec. 7 T. 17 South R. 8 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: XTO ENERGY INC

Well Name: ST OF UT 17-8-7-34

Api No: 43-015-30621 Lease Type: STATE

Section 07 Township 17S Range 08E County EMERY

Drilling Contractor ROSS DRILLING RIG # 1

SPUDDED:

Date 09/15/05

Time NOON

How DRY

Drilling will Commence: _____

Reported by GARY HANCOCK

Telephone # 1-435-749-1632

Date 09/15/2005 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT OR CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 212' FSL x 1,430' FWL COUNTY: EMERY		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
QTR/QR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 08E S STATE: UTAH		9. API NUMBER: 4301530621
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE/COAL

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: CHG PROD CSG/ CMT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. requests approval to add an additional +/- 300 sx light weight cmt (10.5 ppg, 4.14 cuft/sx) ahead of the permitted cmt slurry in order to protect the pipe from corrosion. XTO Energy will attempt to circ cmt to surf.

COPY SENT TO OPERATOR
Date: 9-21-05
Initials: CMT

NAME (PLEASE PRINT) Kelly K. Small TITLE Regulatory Compliance Tech
SIGNATURE *Kelly K. Small* DATE 9/14/2005

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

(5/2000)

DATE 9/20/05 (See Instructions on Reverse Side)
BY *[Signature]*

RECEIVED
SEP 19 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: XTO ENERGY INC.
Address: 2700 FARMINGTON AVE, K #1
city FARMINGTON
state NM zip 87401

Operator Account Number: N-2615 2615
Phone Number: (505) 324-1090

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301530621	STATE OF UTAH 17-8-7-34		SWSE	7	17S	08E	EMERY
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	14944	9/15/2005		9/23/05		
Comments: <u>FRSD</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

KELLY K. SMALL

Name (Please Print)

Kelly K. Small

Signature

Regulatory Compliance Tech 9/19/2005

Title

Date

RECEIVED

SEP 21 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 212' FSL & 1,430' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 T17S R8E S		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530621
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE/COAL
		COUNTY: EMERY
		STATE: UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SPUD & SET
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	CONDUCTOR CSG

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. spudded 17-1/2" hole on 09/15/05. Set 13-3/8" conductor csg @ 41' FS. Cmt'd csg.

NAME (PLEASE PRINT) Kelly K. Small	TITLE Regulatory Compliance Tech
SIGNATURE <i>Kelly K. Small</i>	DATE 9/19/2005

(This space for State use only)

(5/2000)

(See Instructions on Reverse Side)

RECEIVED

SEP 21 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194
2. NAME OF OPERATOR: XTO ENERGY INC.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401	7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 212' FSL & 1,430' FEL	8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
PHONE NUMBER: (505) 324-1090	9. API NUMBER: 4301530621
10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE/COAL	

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 08E S

COUNTY: EMERY

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 9/27/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SET SURF CSG & TD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Drld to 325'. TIH w/8-5/8", 24.0#, J-55, ST&C csg to 317'. Cmtd surf csg w/260 sx Type "G" cmt w/2% KCl & 1/4 PPS Flocele (15.8 ppg, 1.20 cuft/sx). Circ cmt to surf. Reached driller's TD of 4,055' @ 12:00 p.m., 09/26/05. Logged OH. TIH w/5-1/2", 15.5#, J-55, LT&C csg to 3,993.87'. Cmtd prod csg w/450 sx CBM Lite cmt w/1/4 PPS Flocele & 10 PPS Gilsonite (10.5 ppg, 4.14 cuft/sx) followed by 150 sx Type V cmt w/10% Cal-Seal, 1% CaCl2 & 25 PPS Flocele (14.2 ppg, 1.61 cuft/sx). Circ cmt to surf. Released rig.

NAME (PLEASE PRINT) Kelly K. Small

TITLE Regulatory Compliance Tech

SIGNATURE

Kelly K. Small

DATE

10/3/2005

(This space for State use only)

RECEIVED

OCT 06 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 212' FSL x 1,430' FEL COUNTY: EMERY		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 08W S STATE: UTAH		9. API NUMBER: 4301530621
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE/COAL

CONFIDENTIAL

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: SEPT 05 MONTHLY DRLG ACTIVITY
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

COMPLETION SCHEDULED TO START MID OCTOBER 2005.

NAME (PLEASE PRINT) KELLY SMALL TITLE Regulatory Compliance Tech
SIGNATURE *Kelly H Small* DATE 10/5/2005

(This space for State use only)

RECEIVED

OCT 12 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 212' FSL x 1,430' FEL		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 08W S		9. API NUMBER: 4301530621
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE/COAL
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: OCT 05 MONTHLY DRLG ACTIVITY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See attached for October 2005 drilling Activity

NAME (PLEASE PRINT) KELLY SMALL	TITLE Regulatory Compliance Tech
SIGNATURE <i>Kelly Small</i>	DATE 11/7/2005

(This space for State use only)

RECEIVED

NOV 14 2005

DIV. OF OIL, GAS & MINING

Farmington Monthly Report

STATE OF UTAH	Well # 17-08-07-34	FERRON SANDSTON
----------------------	---------------------------	------------------------

Objective: Drill & Complete

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

AFE: 504851

1st Rept: 04/12/2005

10/26/05 Backfill res pit. MI 17 - 500 bbl frac tks. Filled frac tnks w/8,500 BFW (temp 50 deg to 52 deg). Inst 5K 5-1/2" frac vlv. MIRU Big Red Hot Oil. Tstd csg to 4,000 psig for 30". Tstd OK. Heat frac water to 72 deg. MIRU Bran Dex WL. Run CBL fr/3,948' to surf. TOC @ 1,746'. RIH w/4" HSC csg gun. Perf L/Ferron w/3 JSPF fr/3,576' - 3,581' (15 holes), 3,602' - 3,606' (12 holes), 3,609' - 3,611' (6 holes), 3,620' (3 holes) & 3,680' - 3,682' (6 holes) (23 gm, .49" dia, 120 deg phg). All dpts correlated w/Schlumberger CNL/GR log ran on 9/27/05. RIH w/dmp blr & spot 10 gal 28% HCl @ 3,675'. RDMO Bran Dex WL & Big Red Hot Oil. SD WO frac. Build WH mnfd. Build sep & mtr run pad. Set used Pesco 24" x 10' 250 psig WP, 2 ph, vert sep w/250 MBTU burner (SN 23516), heated wtr bath, Daniel 3" 600S mtr run w/Daniel flgs (SN 53519.33) fr/ American West Group et al 15-126. Dug trench fr/WH to sep mtr run. Conn welded 4" S 40 FB FL fr/WH tbg mnfd to sep inl. Conn welded 6" S 40 FB FL fr WH csg mnfd to sep inl w/3" mtr vlv. SDFN.

DWC: \$77,879

CWC: \$373,500

DMC: \$0

CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

10/27/05 MIRU Halliburton. Frac w/5,080 gals 20# Linear Gel, 117,050 gal 20# XL gel (delta 140), carrying 4,500# 40/70 Brady sd, 161,000# 20/40 Brady sd & 71,000# 16/30 Brady Sd (treated w/sd wedge. ATP 1,804 psig. AIR 40 BPM. Max TP 2,567#. ISIP 1,470 psig. 5" SIP 1,346 psig. 10" SIP 1,267 psig. 15" SIP 1,195 psig. MIRU Bran Dex WL. RIH w/5-1/2" CBP & 3-1/8" HSC csg gun. Tgd @ 2,500'. Pmp 10 BFW dwn csg. Could not get below 2,500'. POH CBP & csg gun. RIH 4-3/4" GR. Tgd @ 2,500'. Wrkd to 2,600'. POH GR. Found dark brn oily mtl on GR. SWI. SDFN. 3,016 BLWTR.

DWC: \$220,000

CWC: \$593,500

DMC: \$0

CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

10/28/05 RIH 4-3/4" GR & tgd @ 2,500'. POH GR. Perfs fr/3,576' - 3,682'. TIH 3-5/8" GR & tgd @ 2,500'. POH GR. RDMO Halliburton frac equip & Bran Dex WL. MIRU Key Energy Rig #906. Benco inst anchors. SICP 75 psig. Bd well. Well FARO 50 BLW/hr. NU BOP. SWI. SDFN. 2,816 BLWTR.

DWC: \$7,000

CWC: \$600,500

DMC: \$0

CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

10/29/05 SICP 20 psig. Bd well. TIH w/4-3/4" bit, bit sub & 60 jts 2-7/8" tbg. Bit @ 1,987'. Well FARO 25 BLW/hr. SWI. SDF weather. 2,716 BLWTR.

DWC: \$11,000 CWC: \$611,500 DMC: \$0 CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

10/30/05 SDF weather & Saturday. 2,716 BLWTR.

DWC: \$11,000 CWC: \$622,500 DMC: \$0 CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

10/31/05 SITP 0 psig, SICP 0 psig. Fin TIH w/115 jts 2-7/8" tbg. Tgd. @ 3,780'. PBTD @ 3,948'. Perfs fr/3,576' - 3,682'. TOH & LD 115 jts 2-7/8" tbg. MIRU Bran Dex WL. RIH w/CBP & 4" HSC csg gun. Set CBP @ 3,560'. PT csg to 2,000 psig for 5" w/10 BFW w/rig pmp. Perf U Ferron w/3 JSPF fr/3,461 (3 holes), 3,481' - 3,486' (15 holes), 3,507' - 3,509' (6 holes), 3,515' (3 holes) & 3,530' - 3,539' (27 holes 23 gm, .49" dia, 120 deg phg). All dpts correlated w/Schlumberger CNL/GR log ran on 9/27/05. RDMO Bran Dex WL & Key Energy #906. SWI. WO frac. 2,726 BLWTR.

DWC: \$21,000 CWC: \$643,500 DMC: \$0 CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

Rig: Halliburton

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

11/4/05 MIRU Halliburton frac equip. A. U/Ferron perfs fr/3,461' - 3,539' dwn 5-1/2 csg w/1,000 gal 15% HCL. Frac w/8,519 gals 20# Linear Gel, 142,500 gal 20# XL gel (delta 140) carrying 4,710# 40/70 Brady sd, 205,900# 20/40 Brady sd & 90,500# 16/30 Brady Sd (all trtd w/sd wedge and sd wedge NT). Flshd w/3,330 gals 20# lineral gel. Max sd conc 5.0 ppg. ATP 1,919 psig. AIR 39.5 BPM. Max TP 2,161#. ISIP 1,722 psig. 5" SIP 1,575 psig. 10" SIP 1,488 psig. 15" SIP 1,420 psig. SWI. SDFN. 6,715 BLWTR.

DWC: \$340,000 CWC: \$983,500 DMC: \$0 CMC: \$0

===== STATE OF UTAH #17-08-07-34 =====

RECEIVED

NOV 14 2005

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

DIV. OF OIL, GAS & MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		7. UNIT or CA AGREEMENT NAME _____
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34
2. NAME OF OPERATOR: XTO Energy Inc.		9. API NUMBER: 430153002 30621
3. ADDRESS OF OPERATOR: 2700 Farmington Ave K1 CITY Farmington STATE NM ZIP 87401		10. FIELD AND POOL, OR WILDCAT FERRON SANDSTONE/COAL
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 212' FSL x 1,430' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH: SAME AS SURF		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 8E S
		12. COUNTY EMERY 13. STATE UTAH

14. DATE SPUDDED: 9/15/2005	15. DATE T.D. REACHED: 9/26/2005	16. DATE COMPLETED: 11/21/2005	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 6,610' GL
18. TOTAL DEPTH: MD 4,055 TVD	19. PLUG BACK T.D.: MD 2,482 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) ✓ CAL/AIL/GR/CNL/TLD, MUD (Mailed 10/3), CBL (Mailed 10/7)			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4"	8-5/8 J-55	24.0#		317		G 260		Surf - Circ	
7-7/8"	5-1/2 J-55	15.5#		3,994		CBM 450		1,746' - CBL	
						V 150			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) FERRON	3,481	3,682			3,481 3,682	0.49"	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
3,481' to 3,682'	A. w/1,000 gals 15% HCl ac. Frac'd w/13,599 gals 20# linear gel, 259,550# XL gel (delta 140) carrying 9,210# 40/70, 366,900# 20/40 & 161,500 16/30 Brady sd (w/SW NT).

29. ENCLOSED ATTACHMENTS:

30. WELL STATUS:

- | | | | |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS | <input type="checkbox"/> OTHER: _____ | |

SI

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				MANCOS	3,336
				UPR FERRON SS	3,455
				COAL	3,481
				LWR FERRON SS	3,654
				TUNUNK SH	3,949


35. ADDITIONAL REMARKS (Include plugging procedure)

WELL IN THE PROCESS OF BEING COMPLETED

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) KELLY K. SMALLTITLE REGULATORY COMPLIANCE TECH

SIGNATURE

DATE 11/4/2005

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☒ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48194	
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR: XTO Energy Inc.						6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave K1 CITY Farmington STATE NM ZIP 87401						7. UNIT or CA AGREEMENT NAME	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 212' FSL x 1,430' FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH: SAME AS SURF						8. WELL NAME and NUMBER: STATE OF UTAH 17-8-7-34	
PHONE NUMBER: (505) 324-1090						9. API NUMBER: 4301530622 30621	
10. FIELD AND POOL, OR WILDCAT FERRON SANDSTONE/COAL						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 7 17S 8E S	
12. COUNTY EMERY						13. STATE UTAH	

14. DATE SPUNDED: 9/15/2005	15. DATE T.D. REACHED: 9/26/2005	16. DATE COMPLETED: 11/11/05	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 6,610' GL
18. TOTAL DEPTH: MD 4,055 TVD	19. PLUG BACK T.D.: MD 3,948 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CAL/AIL/GR/CNL/TLD, MUD (Mailed 10/3), CBL (Mailed 10/7)				23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)									
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4"	8-5/8 J-55	24.0#		317		G 260		Surf - Circ	
7-7/8"	5-1/2 J-55	15.5#		3,994		CBM 450		1,746' - CBL	
						V 150			

25. TUBING RECORD								
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	3.878							

26. PRODUCING INTERVALS					27. PERFORATION RECORD				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) FERRON	3,481	3,682			3,481 3,682	0.49"	69	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.	
DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
3,481' to 3,682'	A. w/1,000 gals 15% HCl ac. Frac'd w/13,599 gals 20# linear gel, 259,550# XL gel (delta 140) carrying 9,210# 40/70, 366,900# 20/40 & 161,500 16/30 Brady sd (w/SW NT).

29. ENCLOSED ATTACHMENTS:	30. WELL STATUS:
<input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION	<input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> CORE ANALYSIS <input type="checkbox"/> DST REPORT <input type="checkbox"/> OTHER: _____

RECEIVED

DEC 02 2005

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 11/23/2005		TEST DATE: 11/24/2005		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 173	WATER – BBL: 419	PROD. METHOD: Ppg
CHOKE SIZE: n/a	TBG. PRESS. 110	CSG. PRESS. 60	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 173	WATER – BBL: 419	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				MANCOS	3,336
				UPR FERRON SS	3,455
				COAL	3,481
				LWR FERRON SS	3,654
				TUNUNK SH	3,949

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) KELLY K. SMALL

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE

Kelly K. Small

DATE 11/28/2005

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: XTO Energy Operator Account Number: N 2615
Address: 2700 Farmington Ave, Bldg K Suite 1
city Farmington
state NM zip 87401 Phone Number: (505) 566-7925

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
4301530561	ST of UT 17-8-15-33	NWSE	15	17S	08E	Emery
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
C	14436	13161		8/1/2005		
Comments: frsd = 13161 7th Expansion to Unit PA by SITLA					1/31/07	

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
4301530566	ST of UT 16-8-32-43	NESE	32	16S	08E	Emery
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
C	14719	13161		10/1/2005		
Comments: frsd = 13161 8th Expansion to Unit PA by SITLA					1/31/07	

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
4301530621	ST of UT 17-8-7-34	SWSE	7	17S	08E	Emery
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
C	14944	13161		12/1/2005		
Comments: frsd = 13161 9th Expansion to Unit PA by SITLA					1/31/07	

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Earlene Russell for DOGM

Name (Please Print)

Earlene Russell

Signature

Engineering Technician

1/31/2007

Title

Date

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

4301530621

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER. UTU-73965
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington, Bldg K-1 Farmington NM 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 660' FSK & 792' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESE 10 17S 08E		8. WELL NAME and NUMBER: LM LEMMON #10-01
PHONE NUMBER: (505) 324-1090		9. API NUMBER: Various (see attached)
		10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 1/1/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired wells from Chevron/Texaco on August 1, 2004. Chevron/Texaco failed to file a Notice of Intent to surface commingle these wells and XTO Energy Inc. was unaware until recently that nothing had been filed. We are including with this application for surface commingle a list of the wells in Emery County and a spreadsheet showing production figures for these wells. Each well has its own meter then runs through a central delivery point where allocations are made.

XTO Energy Inc. is requesting approval for the commingle of these wells as well as off-lease measurement. As wells are drilled, additional sundries will be submitted to add to our surface commingle.

COPY SENT TO OPERATOR
Date: 6-12-07
Initials: DM

NAME (PLEASE PRINT) HOLLY C. PERKINS	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE <i>Holly C. Perkins</i>	DATE 5/15/2007

This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 6/11/07
BY: *[Signature]*
(See Instructions on Reverse Side)

Federal Approval Of This
Action Is Necessary

RECEIVED

MAY 18 2007

DIV. OF OIL, GAS & MINING

Utah Wells Surface Commingled at Huntington CDP

Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

Utah Wells Surface Commingled at Huntington CDP

State of Utah FO 02-186	43-015-30533	Producing	State
State of Utah FO 02-188	43-015-30553	Producing	State
State of Utah GG 03-122	43-015-30499	Producing	State
State of Utah GG 04-115	43-015-30504	Producing	State
State of Utah HH 03-133	43-015-30500	Producing	State
State of Utah II 36-95	43-015-30509	Producing	State
State of Utah II 36-96	43-01530508	Shut In	State
State of Utah KK 32-144	43-015-30567	Producing	State
State of Utah QQ 31-201	43-015-30592	Producing	State
State of Utah SS 22-165	43-015-30520	Producing	State
State of Utah T 36-10	43-015-30268	Producing	State
State of Utah T 36-100	43-015-30506	Producing	State
UP&L 06-102	43-015-30441	Producing	State
UP&L 06-103	43-015-30483	Producing	State
UP&L 06-104	43-015-30442	Producing	State
UP&L Federal 01-101	43-015-30511	Producing	Federal
Utah Federal 01-205D	43-015-30589	Producing	Federal
* Utah Federal 16-7-35-21	43-015-30602	Producing	Federal
* Utah Federal 16-7-35-32	43-015-30603	Producing	Federal
* Utah Federal 17-7-12-22D	43-015-30605	Producing	Federal
* Utah Federal 17-7-12-24D	43-015-30604	Producing	Federal
* Utah Federal 17-7-12-42	43-015-30591	Producing	Federal
Utah Federal 17-7-12-43	43-015-30601	Producing	Federal
Utah Federal 17-7-3-41D	43-015-30697	Producing	Federal
Utah Federal KK 01-140	43-015-30507	Producing	Federal
Utah Federal KK 01-141	43-015-30559	Producing	Federal
Utah Federal M 06-25	43-015-30292	Producing	Federal
WH Leonard 15-127	43-015-30485	Producing	State
Wm S Ivie 09-118	43-015-30443	Producing	State
Zion's Federal 35-135R	43-015-30521	Producing	Federal
* Zion's Federal 17-7-2-11	43-015-30590	Producing	Federal
Zion's Federal 35-137	43-015-30587	Producing	Federal

Utah Wells Surface Commingled at Orangeville CDP

Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-95	43-015-30509	Producing	State	
State of Utah II 36-96	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal	
USA 11-72	43-015-30387	Producing	Federal	
USA 18-7-11-23	43-015-30640	Producing	State	
USA 34-80	43-015-30389	Shut In	Federal	
USA 34-82	43-015-30390	Producing	Federal	
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal	
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal	
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal	
Utah Federal D 34-12	43-015-30282	Producing	Federal	
Utah Federal D 35-13	43-015-30285	Producing	Federal	
Utah Federal D 35-14	43-015-30286	Producing	Federal	
Utah Federal D 35-15	43-015-30287	Producing	Federal	
Utah Federal H 06-21	43-015-30294	TA	Federal	
Utah Federal P 10-42	43-015-30276	Producing	Federal	
Utah Federal P 10-43	43-015-30277	Producing	Federal	
Utah Federal P 10-47	43-015-30258	Producing	Federal	
Utah Federal Q 04-44	43-015-30280	Producing	Federal	
Utah Federal R 09-45	43-015-30275	Producing	Federal	
Utah Federal S 08-46	43-015-30274	Producing	Federal	
Utah State 01-76	43-015-30381	Producing	State	
Utah State 36-78	43-015-30382	Producing	State	

Apr-05

Ignition Wells

WELL		Days On	MONTHLY WATER PRODUCTION	FIELD ESTIMATED PRODUCTION										MONTHLY GAS PRODUCTION										ACTUAL ALLOCATED SALES										FIELD PRODUCTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
No.				Coastal Statement	PROD %	FIELD EST. PROD	in Gas	Lse Use Gas	Vented CO2	Vented Gas	VENTED GAS	ADJ	FIELD ESTIMATED SALES	ALLOCATED SALES	Lsa Use Gas	Vented CO2	Vented Gas	VENTED GAS	ADJ	FIELD PRODUCTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									

BTU

Apr 15

the Wells

FIELD ESTIMATED PRODUCTION														ACTUAL ALLOCATED SALES									
Wells	Days On	MONTHLY WATER PRODUCTION	Costal Statement	PROD %	FIELD EST PROD	Irr Gas	Lse Use Gas	Ventod Gas	Ventod Gas	VENTED GAS	ADJ (1)	FIELD ESTIMATED SALES	ALLOCATED SALES	Lse Use Gas (2)	Ventod CO2	Ventod Gas	TOTAL VENTED	TOTAL ADJ (1)	FIELD PRODUCTION				
B21-03	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
A26-02	26	88	490	0.00165775	490	39	13	15	15	15	67	423	432	52	15	15	15	15	67				
C23-08	30	3432	9140	0.03092205	9140	45	235	437	437	437	718	8,422	8,052	281	437	437	437	437	718				
A26-04	5	0	68	0.00023005	68	23	2	2	2	2	26	42	60	24	2	2	2	2	26				
A35-06	30	141	29098	0.09844307	29098	45	750	1706	1706	1706	2,501	26,597	25,665	795	1706	1706	1706	1706	2,501				
A35-05	18	700	289	0.00097773	289	27	7	7	7	7	41	248	255	34	7	7	7	7	41				
A34-07	30	2845	5353	0.01821153	5353	45	139	361	361	361	545	4,838	4,748	184	361	361	361	361	545				
P10-47	30	734	399	0.00047026	399	210	4	6	6	6	229	81	123	214	6	6	6	6	229				
AME PROB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
A27-09	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
U02-11	30	50211	15291	0.05173154	15291	45	394	1,255	1,255	1,255	1,694	13,597	13,487	399	1,255	1,255	1,255	1,255	1,694				
S06-46	29	1	519	0.00175588	519	203	13	230	230	230	446	73	458	216	230	230	230	230	446				
R09-45	30	36	444	0.00150212	444	210	11	102	102	102	323	121	392	221	102	102	102	102	323				
P10-42	29	7609	819	0.0027708	819	44	21	144	144	144	206	610	722	65	144	144	144	144	206				
P10-43	30	3050	605	0.00204681	605	45	16	61	61	61	11	125	54	63	114	11	11	11	125				
O04-44	16	5442	71	0.0002402	71	112	2	11	11	11	11	125	54	63	114	11	11	11	125				
D34-12	24	2583	147	0.00197662	147	36	38	126	126	126	200	1,271	1,297	74	126	126	126	126	200				
D35-13	30	142110	293	0.00091126	293	36	8	57	57	57	101	192	258	44	57	57	57	57	101				
D35-14	24	647	293	0.00091126	293	36	8	57	57	57	101	192	258	44	57	57	57	57	101				
D35-15	30	1830	20903	0.07071811	20903	45	539	1,326	1,326	1,326	1,910	18,993	18,436	584	1,326	1,326	1,326	1,326	1,910				
H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
U02-48	25	7527	2310	0.00781509	2310	42	60	148	148	148	165	2,060	2,037	102	148	148	148	148	165				
U02-50	30	706	2703	0.00914487	2703	45	70	165	165	165	280	2,423	2,384	115	165	165	165	165	280				
U02-49	15	173	347	0.00117395	347	23	9	18	18	18	49	296	305	21	18	18	18	18	49				
10-58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
X16-66	29	307	290	0.00098112	290	42	7	38	38	38	87	203	256	43	38	38	38	38	87				
X16-65	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
14-53	30	298	827	0.00279787	827	45	21	50	50	50	116	711	729	66	50	50	50	50	116				
14-55	30	9023	85522	0.41965343	124,042	90	3,196	7,739	7,739	7,739	11,025	113,017	109,405	3,266	7,739	7,739	7,739	7,739	11,025				
*4-55A	30	58520	58520	0.00091007	269	45	7	22	22	22	85	595	601	63	22	22	22	22	85				
23-51	30	175	259	0.00091007	259	45	18	22	22	22	85	595	601	63	22	22	22	22	85				
24-57	30	254	581	0.00230393	581	45	18	22	22	22	85	595	601	63	22	22	22	22	85				
15-68	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
14-54	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
08-62	29	23	491	0.00166113	491	44	13	179	179	179	235	256	433	55	179	179	179	179	235				
09-60	29	1445	1074	0.00363351	1,074	44	28	154	154	154	269	2,432	2,382	115	154	154	154	154	269				
14-40	30	4320	2701	0.0091379	2,701	45	70	154	154	154	60	201	230	46	154	154	154	154	60				
15-57	26	1202	261	0.000883	261	39	7	14	14	14	14	8,611	8,315	288	14	14	14	14	8,611				
08-61	30	478	9427	0.03189301	9,427	45	243	528	528	528	816	8,611	8,315	288	528	528	528	528	816				
07-54	30	10921	1857	0.00560589	1,857	45	43	495	495	495	583	1,074	1,461	88	495	495	495	495	583				
06-63	30	264	1654	0.00559574	1,654	45	43	495	495	495	583	1,074	1,461	88	495	495	495	495	583				
09-59	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
01-76	30	3108	4980	0.01684812	4,980	45	128	326	326	326	499	4,481	4,392	173	326	326	326	326	499				
35-78	30	903	5802	0.01962907	5,802	45	150	380	380	380	575	5,227	5,117	195	380	380	380	380	575				
03-74	27	24620	1325	0.00448258	1,325	41	34	30	30	30	105	1,220	1,169	75	30	30	30	30	105				
03-75	30	5679	4396	0.01487235	4,396	45	113	299	299	299	457	3,939	3,877	158	299	299	299	299	457				
11-72	30	45297	922	0.00311927	922	45	24	177	177	177	246	675	813	69	177	177	177	177	246				
34-80	15	44	113	0.0003823	113	24	3	21	21	21	48	65	100	27	21	21	21	21	48				
34-82	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
31-98	30	10	1482	0.00501384	1,482	45	38	133	133	133	216	1,266	1,307	83	133	133	133	133	216				
A35-89	30	9902	34803	0.11774398	34,803	45	897	2,021	2,021	2,021	2,953	31,840	30,696	942	2,021	2,021	2,021	2,021	2,953				
P03-92	30	1184	386	0.00299748	386	45	23	89	89	89	157	729	781	68	89	89	89	89	157				
P03-93	28	9434	546	0.00218552	546	42	17	96	96	96	155	491	570	59	96	96	96	96	155				
T22-59	30	320	1130	0.00382297	1,130	45	29	58	58	58	86	460	482	59	58	58	58	58	86				
127-87	30	574	546	0.0018472	546	45	14	27	27	27	73	1,090	1,053	31	27	27	27	27	73				
01-97	30	0	1194	0.00403949	1,194	0	31	27	27	27	73	1,090	1,053	31	27	27	27	27	73				
36-95	30	61	470	0.00159008	470	0	12	49	49	49	61	409	415	12	49	49	49	49	61				
36-95	30	1503	1260	0.00426278	1,260	0	32	130	130	130	162	1,098	1,111	32	130	130	130	130	162				
MERRON GAS WELLS																							
hammer	29	10537	481	0.0016273	481	0	12	15	15	15	27	454	424	12	15	15	15	15	27				
al	4 - 36 - 18 - 7	985	493	0.0016679	493	0	0	28	28	28	28	465	435	0	28	28	28	28	465				
			353007	295582	295562	2,428	7504	20,777	20,777	20,777	30,5												

1E WELLS FROM OASIS STATEMENT

	20777				SALES DIFFERENCE	94.6	JC137.5
	9						
	7604			7604			
	2448		2448				
	0		0				
Id statement + memon	974						
	31803		295682	2448	7604	0	

395211	597033	597137	4379	14975	59724	59724	790771	518060	514853	19355	59724	59724	59724	59724	79079	593932
--------	--------	--------	------	-------	-------	-------	--------	--------	--------	-------	-------	-------	-------	-------	-------	--------

OCT 12 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC. *N2615*

3. ADDRESS OF OPERATOR:
2700 Farmington Bldg K, Suite _____ Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

COUNTY: Emery

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:

Various Leases

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

See attached list

9. API NUMBER:

Multiple

10. FIELD AND POOL, OR WILDCAT:

Buzzard Bench

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC. for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. *N0210*

NAME (PLEASE PRINT) *James L. Death*

TITLE *Vice President-Land*

SIGNATURE *James L. Death*

DATE *8/16/04*

(This space for State use only)

APPROVED *9/30/2004*

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(5/2000)

(See Instructions on Reverse Side)

RECEIVED

SEP 28 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, re-enter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-67532
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1815' FNL & 897' FWL COUNTY: EMERY QTR/QR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 26 18S 07E STATE: UTAH		8. WELL NAME and NUMBER: FEDERAL A 18-7-26 #12
PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530445
		10. FIELD AND POOL, OR WILDCAT: BUZZARD BENCH ABO

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to surface commingle the following two wells into our Orangeville CDP:

Federal A 18-7-26 #12; Sec 26-T18S-R07E; 1815' FNL & 897' FWL; 43-015-30445; UTU-67532; Buzzard Bench
Federal T 18-7-22 #34; Sec 22-T18S-R07E; 539' FSL & 1831' FEL; 43-015-30452; UTU-68535; Buzzard Bench

Both of these wells have their own wellhead allocation meter. Both wells will have the sales point or custody transfer at the Orangeville System.

COPY SENT TO OPERATOR

Date: 7-11-05
Initials: CHO

NAME (PLEASE PRINT) <u>HOLLY C. PERKINS</u>	TITLE <u>REGULATORY COMPLIANCE TECH</u>
SIGNATURE <u>Holly C. Perkins</u>	DATE <u>6/23/2005</u>

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED

JUN 29 2005

DIV. OF OIL, GAS & MINING

(5/2000)

Date: 7/8/05 (See Instructions on Reverse Side)

By: Dustin Ducet
Dustin Ducet ??

IN WELLS FROM COASTAL STATEMENT	0	302425			
	38990				
	104	104			
	256029				
s Check #	0				
s Check #2	0			0	
	7383			7383	0
	1931		1930 5		
	0				
	304437	302529	1930 5	7383	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: MULTIPLE		8. WELL NAME and NUMBER: MULTIPLE St of Ut 17-8-7-34
5. PHONE NUMBER: (505) 333-3100		9. API NUMBER: MULTIPLE 43 015 30621
6. COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT:
7. STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SURFACE
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	COMMINGLE

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. applied for surface commingle on the attached list of wells on 7/5/07 and State of UT DOGM approval was received on 7/13/07. Due to the rejection of the Federal application, XTO would like to withdraw the commingling application and subsequent work will not be done.

NAME (PLEASE PRINT) LORRI D. BINGHAM	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE 	DATE 9/23/2008

(This space for State use only)

RECEIVED
SEP 29 2008

Utah Wells Surface Commingled at Huntington CDP			
Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

should be
on Orangeville
CDP

RECEIVED

SEP 29 2003

DIV. OF OIL, GAS & MINING